

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: **Reserve fund for emergency work in ward no.13** (Improvements to roads and Drains in Basaweshwara Road L/s, near 8th 'D' Cross road, Balance portion in Ward no. 13, in Shettyhalli Sub-

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed Complete as per specification and direction of Engineer-in-charge of the work.4	Cum	22.28	124.02	Rupees One Hundred Twenty Four and Two Paise Only
2	Removing B.S.Slab of drain and stacking. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	41.31	49.18	Rupees Forty Nine and Eighteen Paise Only
3	Refixing stone slabs of drains and pointing in Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	41.31	68.74	Rupees Sixty Eight and Seventy Four Paise Only
4	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	7.29	337.08	Rupees Three Hundred Thirty Seven and Eight Paise Only
5	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	115.20	148.93	Rupees One Hundred Forty Eight and Ninety Three Paise Only
6	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	18.60	4413.84	Rupees Four Thousand Four Hundred Thirteen and Eighty Four Paise Only

Signature of the Contractor
EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Signature
 Executive Engineer

7	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chiselled dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	9.60	5208.84	Rupees Five Thousand Two Hundred Eight and Eighty Four Paise Only
8	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Complete as per specification and direction of Engineer-in-charge of the work.	Cum	9.00	6345.16	Rupees Six Thousand Three Hundred Forty Five and Sixteen Paise Only
9	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 340kgs, with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, Complete as per specification and direction of Engineer-in-charge of the work.	Cum	28.74	5535.32	Rupees Five Thousand Five Hundred Thirty Five and Thirty Two Paise Only
10	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work.	Qtl	15.44	7244.04	Rupees Seven Thousand Two Hundred Forty Four and Four Paise Only
11	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	216.00	311.64	Rupees Three Hundred Eleven and Sixty Four Paise Only

Signature of the Contractor
EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION
BANGALORE-560 010


Executive Engineer

12	Providing & laying reinforced cement precast slabs of mix CC 1:1½:2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	97.20	1600.00	Rupees One Thousand Six Hundred Only
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	137.48	74.07	Rupees Seventy Four and Seven Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer